No: 26-007

DAUPHIN COUNTY SUBDIVISION/LAND DEVELOPMENT REVIEW REPORT

Municipality: Halifax Township | Surveyor: Hoover Engineering | Engineer: Hoover Engineering

Plat Title: 421 Million Dollar Road

Zoning District: N/A (Existing Land Use: Residential/Agricultural) | Proposed Land Use: Residential/Ag.

Plat Status:	___ Preliminary	**Plat Type**:	X Subdivision	**Regulations**:	___ County
	___ Final				X Municipal
	X P/F		___ Land Development		___ Zoning
	X Minor				X S&LD

# of Lots: 2 | # of New Lots: 1 | # of DUs: 1 | Acs Subdiv /Devel: 7.50 | Total Acres: 31.50

Date Received: 12/15/2025 | Staff Review: 12/22/2025 | Official County Review: 12/22/2025

Reviewed by: TS | Checked by: _____ | Tax Map Parcel #: 29-024-041 & 29-024-015

Project Description: Lot addition and creation of 1 new building lot

- *When applicable, streets, sewer, water, storm drainage, and other infrastructure elements to be verified as adequate by municipal staff/engineer. Any improvement guarantees shall be posted prior to final plat approval.*
- *Registered PA Land Surveyor is required to certify all lot/tract boundary descriptions.*
- *When applicable, zoning compliance to be verified by Municipal Zoning Officer.*
- *Appropriate sewage module component should be processed prior to final plat approval.*
- *Final plats must be recorded within 90 days of approval.*

Review comments with cited ordinance provisions are based on municipal regulations on file with the *County Planning Commission.*

Waivers Requested:

S-LD § 404 – Preliminary Plan Requirements

S-LD § 407.1.a.vii – Contour Interval

Comments

1. The plan shall be drawn at a scale not less that 1"=50'. (S-LD § 405.1.a per 407.1.a)
2. All signatures, seals, and notarizations must be acquired upon final plan approval. (S-LD § 407.1.a.xi)
3. All watercourses are required to be displayed on the plan (S-LD § 405.1.a.xii per 407.1.a) There appears to be a stream that runs north/south through the center of Existing Lot 1 on both the north and south side of Million Dollar Road.
4. Any existing and proposed easements are required to be displayed on the plan for reference (S-LD § 405.1.a.ix per 407.1.a) – This includes any existing utilities (underground or overhead) and drainage easements along any watercourses.
5. Drainage easements shall be at least 30' in width. (S-LD § 503.3)
6. Contour intervals of 2 feet are required to be displayed. (S-LD § 407.1.a.vii) The plan shows the applicant's intent to request a modification of this requirement.
7. Curbs on the site may be required in accordance with Section 606 of the Halifax Township SALDO.
8. Sidewalks on the site may be required in accordance with Section 607 of the Halifax Township SALDO.
9. The final Erosion and Sedimentation Control Plan is required to be in accordance with *Section 507* of the Halifax Township Subdivision Ordinance. The reviewer notes that no earth disturbance is proposed with this plan.
10. The final Stormwater Management Plan is required to be in accordance with *Section 508* of the Halifax Township Subdivision Ordinance. The reviewer notes that no earth disturbance is proposed with this plan.


11. Monuments and markers shall be set in accordance with S-LD § 602.
12. Lot area tabulation should be verified for accuracy. According to Dauphin County Parcel Viewer, Existing Lot 1 should be 42.20 acres, while the plan shows 33.5297 acres. It appears the 8.5086 acres of Proposed Lot 2-A were not incorporated in the calculation for Existing Lot 1. Proposed Lot 2 and Proposed Lot 1-A show the same area calculation. Since Proposed Lot 1-A is the lot addition, only the area of the lot addition should be shown for this. Proposed Lot 2 should be the area of Existing Lot 2 plus the area of Proposed Lot 1-A (lot addition).
13. A PennDOT HOP Statement should be added to the plan stating that a PennDOT Highway Occupancy Permit shall be required before access to the state highway is permitted.
14. If the location of the proposed dwelling unit is known at this time, it could be displayed on the plan for reference.

Plan No. 26-007

Plat Specifications	**Yes**	**No**	**N/A**
1. Name of proposed subdivision/land development shown	X		
2. Owner/developer name, address & telephone number shown	X		
3. Municipality name shown	X		
4. Tax parcel number/Deed reference shown/Instrument #	X		
5. North point shown	X		
6. Map scale shown (written/graphic)	X		
7. Date of plan preparation shown	X		
8. Certification of surveyor/engineer/landscape architect shown	X		
9. Location map shown	X		
10. Total property map (bearings, distances, area, primary control point) shown	X		
11. Names of adjacent landowners/subdivision shown	X		
12. Lot numbers shown	X		
13. Lot dimensions shown	X		
14. Lot areas shown (Verify Accuracy)	X		
15. Permanent monuments and markers shown	X		
16. Building setbacks shown	X		
17. Existing natural features shown - Wetlands			X
Floodplains			X
Woodlands, streams, etc.		X	
18. Contours at required interval shown		X	
19. Easements shown and identified		X	
20. Existing man-made features shown - Building (s)	X		
Storm drainage facilities	X		
Sewer mains	X		
Water mains	X		
21. Proposed man-made features shown – Building (s)			X
Storm drainage facilities			X
Sewer disposal – public(X) on-lot ()			X
Water supply – public (X) well ()			X
22. Existing streets shown - Name	X		
R/W width	X		
Paving width	X		
Dedicated R/W width	X		
23. Proposed streets shown - Name			X
R/W width			X
Paving width			X
Profiles			X
24. Curbs shown –			X
25. Sidewalks shown –			X
26. Existing and proposed coverage shown	X		
27. Parking schedule provided shown			X
28. Traffic study completed			X
29. Recreation area shown/fee in-lieu-of provided			X
30. Erosion and sedimentation control plan shown			X
31. Statement of ownership, signature and notarization shown		X	
32. Dedicatory statement shown	X		
33. Approval blocks shown	X		
34. PADOT Highway Occupancy Permit statement shown		X	
35. Consistency with Future Land Use plans - County plans	X		
Municipal plans	X		

MINOR FINAL SUBDIVISION PLAN
OF
421 MILLION DOLLAR ROAD
AND
PARCEL 29-024-015

HALIFAX TOWNSHIP, DAUPHIN COUNTY PENNSYLVANIA



INDEX

1 of 2 - COVER SHEET
2 of 2 - SUBDIVISION PLAN

PLAN DATE: DECEMBER 5, 2025

WAVIER BLOCK			
SECTION	ITEM	APPROVED / DENIED	DATE
404	SUBMISSION OF A PRELIMINARY PLAN		
407,1.a.vii	CONTOUR INTERVAL		

OWNER: PARCEL 29-024-041

RITCHIE V. ENDERS, Jr.
421 MILLION DOLLAR ROAD
HALIFAX, PA 17032
PH. 717 - 319-1153

CERTIFICATION AND DEDICATORY BLOCK

COMMONWEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN

ON THIS, THE _____ DAY OF _____ , 20__ , BEFORE ME, THE UNDERSIGNED PERSONALLY APPEARED

OWNER _____
RITCHIE V. ENDERS, Jr.

WHO BEING DULY SWORN ACCORDING TO LAW, DEPOSES AND SAYS THAT THEY ARE THE OWNERS OF THE PROPERTY SHOWN ON THIS PLAN AND THAT THEY ACKNOWLEDGE THE SAME TO BE THEIR ACT AND DEED AND DESIRE THE SAME TO BE RECORDED AS SUCH ACCORDING TO LAW.

IT IS HEREBY CERTIFIED THAT THE UNDERSIGNED ARE THE LEGAL/EQUITABLE OWNERS OF THE PROPERTY SHOWN ON THIS PLAT AND THAT ALL STREETS OR PARTS THEREOF, IF NOT PREVIOUSLY DEDICATED, ARE HEREBY TENDERED FOR DEDICATION TO PUBLIC USE.

OWNER _____
RITCHIE V. ENDERS, Jr.

WITNESS MY HAND AND NOTORIAL SEAL THE DAY AND THE DATE ABOVE WRITTEN

_____ _____
MY COMMISSION EXPIRES NOTARY PUBLIC

HALIFAX TOWNSHIP PLANNING COMMISSION

THIS PLAN RECOMMENDED FOR APPROVAL BY THE HALIFAX TOWNSHIP PLANNING COMMISSION THIS _____ DAY OF _____ 20 __ .

CHAIRMAN _____

SECRETARY _____

HALIFAX TOWNSHIP BOARD OF SUPERVISORS

THIS PLAN APPROVED BY THE BOARD OF SUPERVISORS OF HALIFAX TOWNSHIP THIS _____ DAY OF _____ 20 __ .

CHAIRMAN _____

SECRETARY _____

CERTIFICATE OF REVIEW
DAUPHIN COUNTY PLANNING COMMISSION

THIS PLAN REVIEWED BY THE DAUPHIN COUNTY PLANNING COMMISSION THIS _____ DAY OF _____ 20 __.

CHAIRMAN _____

SECRETARY _____

CERTIFICATE OF REVIEW
HALIFAX TOWNSHIP ENGINEER

THIS PLAN REVIEWED BY THE HALIFAX TOWNSHIP ENGINEER THIS _____ DAY OF _____ ,20___.

TOWNSHIP ENGINEER _____

RECORDER OF DEEDS CERTIFICATE

THIS PLAN RECORDED IN THE OFFICE OF THE RECORDER OF DEEDS IN AND FOR DAUPHIN COUNTY THIS _____ DAY OF_____ 20 __ .

INSTRUMENT NUMBER _____

PENNSYLVANIA ONE CALL SYSTEM INC. 1-800-242-1776 (TOLL FREE) DIAL 811 TWO FULL BUSINESS DAYS BEFORE YOU DIG

LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE BASED UPON SURFACE EVIDENCE AND EXISTING DRAWINGS AND ARE NOT GUARANTEED TO BE COMPLETE OR ACCURATE BY HOOVER ENGINEERING SERVICES, INC. CONTRACTORS TO CONTACT PA. ONE CALL SYSTEMS, INC. (1-800-242-1776) TO ESTABLISH EXISTING UTILITY LOCATIONS AT LEAST THREE(3) WORKING DAYS PRIOR TO THE START OF ANY EARTHMOVING ACTIVITIES.

HOOVER ENGINEERING SERVICES, INC.
ENGINEERS • PLANNERS • SURVEYORS
658 GAUMER RD. - SUITE 100
NEW CUMBERLAND PA. 17070-2823
TELEPHONE (717) 770-0100 FAX (717) 770-1557

CERTIFICATION OF ACCURACY

I HEREBY CERTIFY THIS PLAN TO BE CORRECT AS SHOWN.

_____ , 20__

_____
CHRIS A. HOOVER, P.E., P.L.S.

225109Sub.dwg

LEGEND

- PROPERTY LINE
- ADJOINING PROPERTY LINE
- MBSL — MINIMUM BUILDING SETBACK LINE
- 500 — 10' CONTOUR INTERVAL
- 502 — 2' CONTOUR INTERVAL
- TREELINE
- SOILS BOUNDARY LINE
- PROPERTY CORNER - TO BE SET
- PROPERTY CORNER - FOUND
- P1 : : : P2 — SOILS TESTING AREA
- STORM SEWER
- UTILITY POLE
- OHE — OVERHEAD ELECTRIC LINE
- UGE — UNDERGROUND ELECTRIC LINE

PROPERTY LINE INFORMATION :

(A) – R=7,671.95' AL=137.60' CB=S 88°02'07" E CD=137.60'
(B) – S 12°56'39" E – 30.97'
(C) – S 12°56'39" E – 108.20'
(D) – S 82°33'21" W – 156.93'
(H) – R=7,671.95' AL=89.93' CB=S 88°53'06" E CD=89.93'
(E) – R=7,701.95' AL=142.01' CB=S 88°04'41" E CD=142.01'
(F) – R=7,701.95' AL=82.74' CB=S 88°54'50" E CD=82.74'
(G) – S 89°41'52" E – 16.72'
(I) – S 00°18'08" W – 30.00'
(J) – S 00°18'08" W – 46.62'
(K) – S 89°41'52" E – 32.56'
(L) – R=233.11' AL=138.58' CB=N 74°52'12" E CD=136.55'
(M) – R=726.56' AL=250.28' CB=N 66°15'55" E CD=249.04'
(N) – R=1,544.86' AL=69.64' CB=N 74°26'20" E CD=69.63'
(O) – S 89°41'52" E – 16.59'
(P) – R=7,671.95' AL=73.38' CB=N 87°14'52" W CD=73.32'

SITE DATA :

TAX MAP PARCEL NUMBER: LOT 1 : 29-024-041-000-0000
LOT 2 : 29-024-015-000-0000
SOURCE OF TITLE : LOT 1 : 20250014003
LOT 2 : 0490500185
TOTAL NUMBER OF LOTS = 2
PROPOSED NUMBER OF LOTS = 3
LENGTH OF NEW STREET = N/A
LENGTH OF STORM SEWER = N/A
METHOD OF SEWAGE DISPOSAL - PRIVATE
METHOD OF WATER SUPPLY - PRIVATE ON LOT WELL
USE OF LAND - RESIDENTIAL AND AGRICULTURAL

LOT CRITERIA : ON-LOT WATER AND SEWER

ON-LOT WATER AND SEWER :
MINIMUM LOT AREA = 1.5 AC.
MINIMUM LOT WIDTH = 150 FT.
MAXIMUM IMPERVIOUS COVERAGE = 30%
MINIMUM FRONT YARD : 30 FT.
MINIMUM SIDE YARD : 20 FT.
MINIMUM REAR YARD : 25 FT.
MAXIMUM PERMITTED HEIGHT : 35 FT.

LOT AREA TABULATION PRIOR TO SUBDIVISION:

LOT 1 = GROSS 1,460,555.18 S.F. / 33.5297 AC.
= NET 1,434,182.14 S.F. / 32.9243 AC.

LOT 2 = GROSS 21,851.48 S.F. / 0.5016 AC.
= NET 17,658.58 S.F. / 0.4054 AC.

POST SUBDIVISION:

LOT 1 = GROSS 1,430,100.35 S.F. / 32.8306 AC.
= NET 1,406,817.54 S.F. / 32.2961 AC.

LOT 2 = GROSS 52,306.31 S.F. / 1.2008 AC.
+ LOT 1-A = NET 45,023.19 S.F. / 1.0336 AC.


LOT 2-A = GROSS 370,635.47 S.F. / 8.5086 AC.
= NET 344,199.19 S.F. / 7.9017 AC.

SOIL TYPE INFORMATION :

At - ATKINS SILT LOAM
CkC2 - CALVIN - KLINESVILLE SHALY SILT LOAMS, 8 TO 15% SLOPES, MODERATELY ERODED
CkD2 - CALVIN - KLINESVILLE SHALY SILT LOAMS, 15 TO 25%SLOPES, MODERATELY ERODED
ClB2 - CALVIN - LECK KILL SHALY SILT LOAMS, 3 TO 8% SLOPES, MODERATELY ERODED
KaC2 - KLINESVILLE SHALY SILT LOAM, 8 TO 15% SLOPES, MODERATELY ERODED
KaE2 - KLINESVILLE SHALY SILT LOAM, 25 TO 50% SLOPES, MODERATELY ERODED

GENERAL NOTES :

1. THE PURPOSE OF THIS PLAN IS TO SUBDIVIDE THE PROPERTY LOCATED ALONG MILLION MILE ROAD (ENDERS FARM) INTO THREE LOTS. LOT 1 WILL BE THE RESIDUAL TRACT WHICH WILL REMAIN IN AGRICULTURAL USE. LOT 1-A WILL BE A LOT ADDITION TO 421 MILLION MILE ROAD (LOT 2). A NEW DEED OF CONSOLIDATION SHALL BE PREPARED COMBINING LOTS 2 AND 1-A INTO ONE LOT AND RECORDED IN THE DAUPHIN COUNTY RECORDER OF DEEDS OFFICE IN CONJUNCTION WITH THE RECORDING OF THE SUBDIVISION PLAN. LOT 2-A WILL BE A PROPOSED LOT TO BE USED FOR A SINGLE FAMILY RESIDENTIAL HOME.
2. PERIMETER INFORMATION AS SHOWN IS BASED UPON THE FOLLOWING:
   a. A FIELD SURVEY PERFORMED BY HOOVER ENGINEERING SERVICES, INC. SURVEY PERFORMED AUGUST, 2025.
   b. SITE DEED REFERENCES RECORDED IN THE OFFICE OF THE RECORDER OF DEEDS FOR DAUPHIN COUNTY.
   i. INSTRUMENT 20250014003.
   ii. INSTRUMENT 0490500185.
3. TOPOGRAPHIC INFORMATION AND EXISTING FEATURES AS SHOWN ARE BASED UPON A FIELD SURVEY PERFORMED BY HOOVER ENGINEERING SERVICES, INC, IN SEPTEMBER, 2025. ADJACENT TOPOGRAPHIC INFORMATION TAKEN FROM P.A.S.D.A. LIDAR MAPPING INFORMATION. CONTOUR INFORMATION BASED UPON 1988 NGV DATUM.
4. THERE ARE NO WETLANDS LOCATED ON EITHER LOTS 1 OR 2 BASED UPON REVIEW OF THE NATIONAL WETLAND INVENTORY MAPPING. HOWEVER, SOME OF THE SOILS LOCATED ON THE SITE ARE HYDRIC OR MAY HAVE HYDRIC INCLUSIONS. COMPLIANCE WITH STATE AND FEDERAL WETLAND STAUTES AND REGULATIONS IS NECESSARY BEFORE WETLANDS ARE FILLED OR ENCROACHED UPON BY STRUCTURES OR EARTH DISTURBANCE. THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION SHOULD BE CONTACTED FOR GUIDANCE IF ANY EARTHWORK IS UNDERTAKEN.
5. UTILITIES AS SHOWN ARE BASED UPON FIELD SURVEYED INFORMATION, RECORDED SUBDIVISION AND LAND DEVELOPMENT PLANS, AND INFORMATION PROVIDED BY OTHERS. HOOVER ENGINEERING SERVICES, INC., DOES NOT WARRANT OR GUARANTEE THE ACCURACY OF SAID LOCATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL UTILITY LOCATIONS PRIOR TO START OF ANY CONSTRUCTION. THE CONTRACTOR SHALL SAFEGUARD ALL UTILITIES DURING CONSTRUCTION IF IT OCCURS.
6. IRON PINS SHALL BE PLACED AT ALL PROPOSED PROPERTY CORNERS WHERE NO MONUMENTATION CURRENTLY EXISTS AS INDICATED, AND CONCRETE MONUMENTS SHALL BE PLACED WHERE INDICATED. MARKERS AND MONUMENTS SHALL BE PER THE REQUIREMENTS OF THE HALIFAX TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCE.
7. NO KNOWN PROTECTIVE COVENANTS OR DEED RESTRICTIONS ARE ASSOCIATED WITH THIS PROPERTY BASED UPON REVIEW OF THE EXISTING DEEDS. LOT 1 IS ENROLLED IN THE CLEAN AND GREEN PROGRAM WITH DAUPHIN COUNTY. THE APPLICANT SHOULD BE AWARE THAT SUBDIVISION OF THE ENROLLED PARCEL MAY RESULT IN FUTURE TAX RESPONSIBILITIES.
8. NEITHER LOT 1 NOR LOT 2 IS LOCATED WITHIN A MAPPED 100-YEAR FLOODPLAIN BASED UPON A REVIEW OF F.E.M.A. MAPPING FOR HALIFAX TOWNSHIP, DAUPHIN COUNTY, PANEL 42043C0095D, EFFECTIVE DATE 8/2/2012. SAID FLOODPLAIN IS ZONE X, AN AREA OF MINIMAL FLOOD HAZARD.
9. THE APPLICANT AGREES TO COMPLY WITH ALL APPLICABLE REGULATIONS IN EFFECT AT THE TIME OF THE PLAN SUBMISSION.
10. NOTHING SHALL BE PLACED, PLANTED, SET OR PUT WITHIN THE AREA OF AN EASEMENT THAT WOULD ADVERSELY AFFECT THE FUNCTION OF THE EASEMENT OR CONFLICT WITH THE EASEMENT AGREEMENT.
11. THERE ARE NO KNOWN EXISTING WAIVERS, VARIANCES, SPECIAL EXCEPTIONS OR CONDITIONAL USES ASSOCIATED WITH THIS PROPERTY.
12. NO BUILDING PERMIT WILL BE ISSUED UNTIL A TOWNSHIP HIGHWAY OCCUPANCY PERMITTEE HAS BEEN ISSUED.
13. PRIOR TO THE DEVELOPMENT OF LOT 2-A WITH A SINGLE FAMILY HOME, AN EROSION CONTROL AND STORMWATER MANAGEMENT PLAN SHALL BE PREPARED AND REVIEWED BY THE DAUPHIN COUNTY CONSERVATION DISTRICT AND/OR HALIFAX TOWNSHIP.
14. AN INGRESS AND ACCESS EASEMENT SHALL BE PROVIDED AS INDICATED AT THE EXISTING DRIVEWAYS AS SHOWN TO PROVIDE ACCESS TO LOTS 2 AND 2-A, AS WELL AS LANDS NOW OR LATE OF LIND WHO CURRENTLY USES THE NORTHERN DRIVEWAY.


PROPOSED LOT 2-A GROSS 370,635.47 S.F. 8.5086 AC. NET 344,199.19 S.F. 7.9017 AC.
EXISTING LOT 1 GROSS 1,460,555.18 S.F. 33.5297 AC. NET 1,434,182.14 S.F. 32.9243 AC.
EXISTING LOT 2 GROSS 21,851.48 S.F. 0.5016 AC. NET 17,658.58 S.F. 0.4054 AC.
PROPOSED LOT 1-A GROSS 52,306.31 S.F. 1.2008 AC. NET 45,023.19 S.F. 1.0336 AC.
PROPOSED LOT 2 GROSS 52,306.31 S.F. 1.2008 AC. NET 45,023.19 S.F. 1.0336 AC.
PROPOSED LOT 1 GROSS 1,430,100.35 S.F. 32.8306 AC. NET 1,406,817.54 S.F. 32.2961 AC.
MILLION DOLLAR ROAD
EXISTING DWELLING
EX. WELL
EX. GRAVEL DRIVEWAY
EX. C/O
EX. SEPTIC AREA
SEPTIC TANK (TYP.)
EX. TREE
EX. FILL PILE
EX. CHICKEN COOP
EX. SHED
EX. CONC.
EX. ELEC. TOWER
EX. POWER LINE EASEMENT
POSSIBLE WELL LOCATION
WOODED AREA
MINIMUM BUILDING SETBACK LINE
EX. 40 MPH SIGN
PRIMARY CONTROL POINT
N/A AMEER FARHAT TMP. 29-024-0020.0--00000 INST. No. 20230002494
N/A JAMES ANDERS TMP. 29-024-0035.0--00000 INST. No. 20210034355
N/A CINDY M. LIND TMP. 29-024-0030.0--00000 INST. No. 20230039932
N/A MICHAEL L. SEIPPS TMP. 29-024-0040.0--00000 INST. No. 20200010685
N/A RUSTY L. BROWN TMP. 29-024-0045.0--00000 INST. No. 20200010685
N/A MICHAEL L. SEIPPS TMP. 29-024-0040.0--00000 INST. No. 4851405
N/A TIM L. GARDNER TMP. 29-028-0040.0--00000 INST. No. 20170004023167
N/A TIM L. GARDNER TMP. 29-028-0040.0--00000 INST. No. 0478500617
R=7,641.95' L=99.56' CHDB=N86° 36' 05"W CHDD=99.56'
R=7641.949 L=299.47' CHDB=S88° 05' 50"E CHDD=299.45'
R=203.106 L=120.79' CHDB=N74° 58' 40"E CHDD=119.02'
R=756.557 L=260.11' CHDB=S66° 16' 35"W CHDD=258.83'
R=1514.860 L=140.03' CHDB=N73° 04' 42"E CHDD=139.98'
R=1,574.86' L=81.31' CHDB=N74° 15' 19"E CHDD=81.30'
R=696.56' L=240.41' CHDB=N66° 15' 17"E CHDD=239.22'
R=263.11' L=156.35' CHDB=N74° 46' 49"E CHDD=154.03'
R=7,701.95' L=177.94' CHDB=N86° 53' 16"W CHDD=177.94'
N 34°21'35" E 245.43'
N 73°51'35" E 416.10'
N 31°11'42" E 386.10'
N 40°22'24" E 391.58'
N 43°37'29" W 235.27'
S 36°38'24" E 308.00'
S 72°31'35" W 82.91'
S 35°40'02" E 389.12'
S 89°41'52" E 32.14'
S 35°55'25" E 400.78'
N 41°09'54" E 83.19'
S 35°55'25" E 853.75'
S 35°55'25" E 1,097.25'
N 35°55'25" W 1,097.25'
N 54°25'35" W 889.08'
N 40°22'24" E 32.58'
S 40°22'24" W 43.50'
S 12°56'39" E 108.20'
S 12°56'39" E 30.97'
S 82°33'21" W 156.93'
S 12°56'39" E 28.28'
S 12°56'39" E 96.72'
S 12°56'39" E 32.96'
S 12°56'39" E 32.96'
S 12°56'39" E 32.96