No: 26-083

DAUPHIN COUNTY SUBDIVISION/LAND DEVELOPMENT REVIEW REPORT

Municipality Derry Township Surveyor Marquiss Engineer/RLA Geist

Plat Title Proposed Building Addition at Best Western Plus

Zoning District Palmdale Mixed Use (E Choc Ave Overlay – O10) Proposed Land Use Hotel

Plat Status: ___ Preliminary; ___ Final; X P/F; ___ Minor

Plat Type: ___ Subdivision; X Land Development

Regulations: ___ County; X Municipal; X Zoning; X S&LD

Existing # of Lots 2 | Proposed # of Lots 2 | Proposed # of New DUs 0 | Subdivided / Developed Acres 0.02 | Total Acres 2.16

Date Received 08/07/26 Staff Review 08/20/26 Official County Review 08/20/26

Reviewed by DMK Checked by _____ Tax Map Parcel # 24-007-127; -218; -130


- *When applicable, streets, sewer, water, storm drainage, and other infrastructure elements to be verified as adequate by municipal staff/engineer. Any improvement guarantees shall be posted prior to final plat approval.*
- *Registered PA Land Surveyor is required to certify all lot/tract boundary descriptions.*
- *When applicable, zoning compliance to be verified by Municipal Zoning Officer.*
- *Appropriate sewage module component should be processed prior to final plat approval.*
- *Final plats must be recorded within 90 days of approval.*

Review comments with cited ordinance provisions are based on municipal regulations on file with the *County Planning Commission.*

1. The following certifications, signatures and approvals (or approved waivers) are required prior to plan recording:
   a. Surveyor/engineer name, seal and signature [S-LD §185-13E(4a)(32, 33)]
   b. Ownership and dedicatory statements with notarization [S-LD §185-13E(4a)(46, 47)]
   c. Erosion and sedimentation control [S-LD §185-13E(4a)22]
   d. Stormwater management plan [S-LD §185-13E(5f);185-26]
   e. DEP sewage planning module [S/LD – §185-13E(5b)]
   f. Lighting plan and professional certification [S-LD §185-33E]
2. Provide correct addresses in the area and bulk regulations chart on Sheet 01. In addition, include parcel 24-007-130 in the parcel listing, as well as existing and proposed acres for each parcel/address included on the chart.
3. Show appropriate monument/marker(s) for adjusted property line of parcel 24-007-130 [S-LD §185-13E(4a)(49)].
4. Provide data substantiating minimum fire hydrant flow, availability, recharge and duration requirements [S-LD §185-12D(4g); §185-36B (7)].
5. Provide an updated lighting plan and details of light standards and fixtures to be used for any additional lighting provided with the building expansion. The plan is required to be certified by a professional engineer [S-LD §185-33E, H].
6. Provide any other reasonable data the Township may require to evaluate the proposal [S-LD §185-13E(5f)].

Plan No. 26-083

Plat Specifications	Yes	No	N/A
1. Name of proposed subdivision/land development shown	✓		
2. Owner/developer name, address & telephone number shown	✓		
3. Municipality name shown	✓		
4. Tax parcel number/Deed reference shown/Instrument #	✓		
5. North point shown	✓		
6. Map scale shown (written/graphic)	✓		
7. Date of plan preparation shown	✓		
8. Certification of surveyor/engineer shown *(need seals, signatures)*	✓		
9. Location map shown	✓		
10. Total property map (bearings, distances, area, primary control point) shown	✓		
11. Names of adjacent landowners/subdivision shown	✓		
12. Lot numbers shown	✓		
13. Lot dimensions shown *(as surveyed)*	✓		
14. Lot areas shown	✓		
15. Permanent monuments and markers shown *(need for lot line adjustment)*		✓	
16. Building setbacks shown	✓		
17. Existing natural features shown - Wetlands			✓
Floodplains			✓
Woodlands, streams			✓
18. Contours at required interval shown	✓		
19. Easements shown and identified	✓		
20. Existing man-made features shown - Building (s)	✓		
Storm drainage facilities	✓		
Sewer mains	✓		
Water mains	✓		
21. Proposed man-made features shown – Building (s)	✓		
Storm drainage facilities	✓		
Sewer disposal – public (✓) on-lot ( )	✓		
Water supply – public (✓) well ( )	✓		
22. Existing streets shown - Name	✓		
R/W width	✓		
Paving width	✓		
Dedicated R/W width	✓		
23. Proposed streets shown - Name			✓
R/W width			✓
Paving width			✓
Profiles			✓
24. Curbs shown	✓		
25. Sidewalks shown	✓		
26. Existing and proposed coverage shown	✓		
27. Parking schedule provided shown	✓		
28. Traffic study completed			✓
29. Recreation area shown/fee in-lieu-of provided			✓
30. Erosion and sedimentation control plan shown	✓		
31. Statement of ownership, signature and notarization shown *(needs sign/notar)*	✓		
32. Dedicatory statement shown			✓
33. Approval blocks shown	✓		
34. PADOT Highway Occupancy Permit statement shown	✓		
35. Consistency with Future Land Use plans - County plans	✓		
Municipal plans	✓		



VICINITY MAP
SCALE = 1" = 800'

N
800' 400' 0' 800'
SCALE: 1"= 800'

PRELIMINARY/FINAL SUBDIVISION AND LAND DEVELOPMENT PLAN


PROPOSED BUILDING ADDITION

AT

BEST WESTERN PLUS

DERRY TOWNSHIP

DAUPHIN COUNTY, PENNSYLVANIA



LOCATION MAP
SCALE = 1" = 1,000'

N
1,000' 500' 0' 1,000'
SCALE: 1"= 1,000'

ACT 287 LIST OF UTILITIES

THE CONTRACTOR SHALL COMPLY WITH THE PROVISIONS OF ACT 287 OF 1974 AS AMENDED BY ACT 187 OF 1996 FOR NOTIFICATION OF UTILITIES BEFORE EXCAVATION IN CONTRACT AREA. THE ONE UNDERGROUND UTILITIES LOCATION CALL NUMBER IS 1-800-242-1776. DESIGN SERIAL NUMBER IS 20253352479, SUBMITTED ON 12/1/2025.

UTILITIES:

COMPANY: COMCAST
ADDRESS: 1241 PA-66 BUS
GREENSBURG, PA 15601
CONTACT: ASHLEY DONALDSON
EMAIL: ASHLEY_DONALDSON@COMCAST.COM
PHONE: 412-925-3236

COMPANY: AT&T
ADDRESS: 1100 3RD AVENUE
ALTOONA, PA 16602
CONTACT: PAT SUTTON
EMAIL: PS4364@ATT.COM
PHONE: 814-321-6470

COMPANY: DERRY TOWNSHIP MUN AUTH
ADDRESS: 670 CLEARWATER RD
HERSHEY, PA 17033
CONTACT: MICHAEL STOTLER
EMAIL: MSTOTLER@DTMA.COM
PHONE: 717-566-3237 EXT. 311

COMPANY: USIC LOCATING SERVICES LLC
ADDRESS: 9045 N RIVER ROAD SUITE 300
INDIANAPOLIS, IN 46240
CONTACT: USIC DISPATCH
PHONE: 800-778-9140

COMPANY: PENNSYLVANIA ELECTRIC CO
ADDRESS: 341 WHITE POND DRIVE
AKRON, OH 44320
CONTACT: MELLYSSA ADAMS
EMAIL: MADAMS@FIRSTENERGYCORP.COM
PHONE: 330-252-4013

COMPANY: PENNSYLVANIA-AMERICAN WATER CO
ADDRESS: 200 CANAL ST
HUMMELSTOWN, PA 17036
CONTACT: MICHAEL RAGER
E-MAIL: MICHAEL_RAGER@AMWATER.COM
PHONE: 717-554-0045

COMPANY: PPL ELECTRIC UTILITIES CORPORATION
ADDRESS: 437 BLUE CHURCH RD
PAXINOS, PA 17860
CONTACT: DOUG HAUPT
E-MAIL: DLHAUPT@PPLWEB.COM
PHONE: 570-490-5684

COMPANY: VERIZON NORTH
ADDRESS: 31 S BEAVER ST
YORK, PA 17401
CONTACT: DAVID NEWMISTER
EMAIL: DAVE.NEWMISTER@VERIZON.COM
PHONE: 717-515-9815

COMPANY: UGI UTILITIES INC
ADDRESS: 1301 AIP DR
MIDDLETOWN, PA 17057-5987
CONTACT: GEOFFREY FERGUSON
EMAIL: GFERGUSON@UGI.COM
PHONE: 610-807-3118



CDC	MEMBER NAME	RESPONSE	RESPONSE DATE	INITIALS
AQ1	COMCAST	**DID NOT RESPOND THROUGH PA ONE CALL.**		
ATM	AT&T	**CLEAR. NO FACILITIES OR FACILITIES NOT INVOLVED BASED ON TICKET INFORMATION.**	12/1/2025 14:08	SYS-WEBSVC
DF	DERRY TOWNSHIP MUN AUTH/DERRY TOWNSHIP	**DESIGN CONFLICT. PLEASE EMAIL OR SEND PLANS TO:** **MICHAEL STOTLER** **DERRY TOWNSHIP MUN AUTH/DERRY TOWNSHIP** **670 CLEARWATER RD** **HERSHEY PA 17033** **MSTOTLER@DTMA.COM**	12/2/2025 13:11	DN-OTM
ION	FIRSTLIGHT FIBER	**CLEAR. NO FACILITIES OR FACILITIES NOT INVOLVED BASED ON TICKET INFORMATION.**	12/3/2025 10:35	CLS-WEBSVC
ME	METROPOLITAN EDISON CO/FIRSTENERGY	**ENGINEERING COMPLETED. A PDF FILE OR MARKED UP PLANS WERE SENT TO THE REQUESTOR.**	12/1/2025 14:16	MBR-WEBSVC
PH	PENNSYLVANIA AMERICAN WATER	**ENGINEERING COMPLETED. A PDF FILE OR MARKED UP PLANS WERE SENT TO THE REQUESTOR.**	12/2/2025 8:22	BLA-WEBSVC
PRD	PPL ELECTRIC UTILITIES CORPORATION	**DID NOT RESPOND THROUGH PA ONE CALL.**		
TI	VERIZON NORTH	**DID NOT RESPOND THROUGH PA ONE CALL.**		
UI	UGI UTIL HARRISBURG	**ENGINEERING COMPLETED. A PDF FILE OR MARKED UP PLANS WERE SENT TO THE REQUESTOR.**	12/4/2025 10:56	AAA-WEBSVC

PLAN PREPARERS

INTEGRATED CONSULTING
4 KACEY COURT
MECHANICSBURG | PA | 17055

CONTACT: ZANE GEIST, P.E.
TELEPHONE: 724-304-1043
EMAIL ADDRESS: ZANE@INTEGRATEDDP.COM

APPLICANT AND DEVELOPER

SWEET HOTELS, LLC
1800 CHOCOLATE AVENUE
HERSHEY, PA 17033

CONTACT: RUPAL PATEL
TELEPHONE: 717-919-8280
EMAIL ADDRESS: RUPAL@KUNJINC.COM

LANDOWNER

SWEET HOTELS, LLC
1800 CHOCOLATE AVENUE
HERSHEY, PA 17033
CONTACT: RUPAL PATEL
TELEPHONE: 717-919-8280
EMAIL ADDRESS: RUPAL@KUNJINC.COM

PALMDALE HOTEL CONDOMINIUM ASSOCIATION
1806 CHOCOLATE AVE
HERSHEY, PA 17033
CONTACT: RUPAL PATEL
TELEPHONE: 717-919-8280
EMAIL ADDRESS: RUPAL@KUNJINC.COM

RUPAL PATEL
1830 CHOCOLATE AVE
HERSHEY, PA 17033
CONTACT: RUPAL PATEL
TELEPHONE: 717-919-8280
EMAIL ADDRESS: RUPAL@KUNJINC.COM

SURVEYOR

INTEGRATED CONSULTING
4 KACEY CT
MECHANICSBURG, PA 17055

CONTACT: JASON MARQUISS, SU075715
TELEPHONE: 724-304-1043
EMAIL ADDRESS: JASON@INTEGRATEDDP.COM

SITE DATA

GROSS/NET TRACT AREA:	87,674 SF / 2.01 AC. (SEE NDA CALCULATIONS BELOW)
PROPOSED NUMBER OF LOTS:	2 EX. LOTS
WATER SERVICE:	PUBLIC
SANITARY SEWER SERVICE:	PUBLIC

NET DEVELOPABLE AREA (NDA)

NDA OF EXISTING RIGHT-OF-WAY	= 0 SF	*0.0 = 0 SF
NDA OF FLOODWAYS/FLOOD FRINGE	= 0 SF	*0.1 = 0 SF
NDA OF STREAMS / PONDS	= 0 SF	*0.1 = 0 SF
NDA OF WETLANDS	= 0 SF	*0.1 = 0 SF
NDA OF NATURAL SLOPES +30%	= 0 SF	*0.1 = 0 SF
NDA OF NATURAL SLOPES 20-30%	= 0 SF	*0.5 = 0 SF
NDA OF NATURAL SLOPES 10-20%	= 0 SF	*0.7 = 0 SF
NDA OF QUARRIES/NEARBY QUARRIES	= 0 SF	*0.0 = 0 SF
NDA OF CEMETERIES	= 0 SF	*0.0 = 0 SF
NDA OF LANDFILLS	= 0 SF	*0.0 = 0 SF
NDA OF ALL OTHER AREAS	= 87,633 SF	*1.0 = 87,674 SF
TOTAL NDA OF TRACT	**= 87,633 SF / 2.01 ACRES**	
UNDEVELOPABLE AREA	**= 0 SF / 0.00 ACRES**	

PLAN PURPOSE

THE PURPOSE OF THIS PLAN IS TO PROPOSE THE CONSTRUCTION OF A NEW BUILDING ADDITION CONSISTING OF 13 GUEST ROOMS AND MANAGERS APARTMENT TO THE EXISTING BEST WESTERN PLUS HOTEL AND A LOT ADJUSTMENT WITH NEIGHBORING ADDRESS 1830 CHOCOLATE AVE. ALONG WITH ASSOCIATED IMPROVEMENTS SHOWN HEREON.

WAIVER REQUEST

THE APPLICANT IS HEREBY REQUESTING THE FOLLOWING WAIVER(S) FROM THE DERRY TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCE:

WAIVER TYPE:		APPROVAL DATE
SECTION 185-12-D-3-A-9	LOCATION OF ALL EXISTING STRUCTURES WITHIN 200 FEET OF TRACT	
SECTION 185-12-D-3-A-21,22,23	PROFILES OF EXISTING STORM, SANITARY, GAS & WATERLINES	
SECTION 185-12-E-4-A-19,20,21	PROFILES OF PROPOSED GAS AND WATERLINES	
SECTION 185-12-D-3-A-35	TOPOGRAPHIC LAND CONTOURS WITHIN 200 FEET OF THE PERIMETER	
SECTION 185-22-D-2&3	ALLEY WIDENING	

AREA AND BULK REGULATIONS

LOCATION:	1806 & 1830 EAST CHOCOLATE AVENUE, HERSHEY, PA 17033						
PARCEL(S):	24-007-127, 24-007-218						
ZONE:	PALMDALE MIXED USE (PMU) DISTRICT, EAST CHOCOLATE AVENUE OVERLAY (O10) & CENTRAL MASTER PLAN APPROVAL AREA (PER §225-314 - MAP 16)						
USE:	HOTELS AND MOTELS (PERMITTED WITHIN O10 OVERLAY)						
				1800 E CHOCOLATE AVE		1830 E CHOCOLATE AVE	
#	ITEM	SECTION	REQUIREMENTS	EXISTING	PROPOSED	EXISTING	PROPOSED
1	MINIMUM LOT WIDTH	§225-314 - TABLE 27.A. (O10)	40 FT @ SETBACK LINE & STREET R/W LINE	229 FT	229 FT	36 FT**	36 F**
2	MINIMUM LOT DEPTH	§225-314 - TABLE 27.B. (O10)	100 FT @ SHALLOWEST LENGTH PERPENDICULAR TO THE STREET R/W LINE	271 FT	271 FT	148FT	110 FT
3	MINIMUM FRONT YARD	§225-314 - TABLE 27.D. (O10)	20 FT	7.2 FT (MOTEL) *	PROPOSED: 25.7 FT (PR. ADDITION)	13 FT***	13 FT***
4	MINIMUM SIDE YARD (LOTS > 85 FT WIDE)	§225-314 - TABLE 27.E. (O10)	15 FT	EXISTING: 6.5 FT (EX. MOTEL BUILDING) **	PROPOSED: 8.9 FT (PR. ADDITION) **	8.2 FT***	8.2 FT***
5	MINIMUM REAR YARD	§225-314 - TABLE 27.F. (O10)	25 FT	65.0 FT (EX. HOTEL BUILDING)	65.0 FT (EX. HOTEL BUILDING)	3.1 FT***	3.1 FT***
6	MAXIMUM BUILDING HEIGHT (PRINCIPAL STRUCTURE)	§225-314 - TABLE 27.G. (O10)	45 FT	44.5 FT	44.5 FT	<45 FT	<45 FT
7	MAXIMUM IMPERVIOUS COVERAGE	§225-314 - TABLE 27 (O10)	60% (52,604 SF)	55.8% (48,952 SF) (1.12 AC)	57.1% (50,921 SF) (1.16 AC)	55.7% (3,703 SF) (0.09 AC)	44.5% (2,567 SF) (0.05 AC)
8	MINIMUM VEGETATED COVERAGE	§225-314 - TABLE 27 (O10)	30% (26,302 SF)	31.7% (27,776 SF) (0.64 AC)	30.1% (26,788 SF) (0.61 AC)	44.3% (2,945 SF) (0.07 AC)	55.4% (3,199 SF) (0.07 AC)
9	MINIMUM PARKING RATIOS FOR HOTELS & MOTELS	§225-402.5. - TABLE 35	1 SPACE / GUEST ROOM W/O KITCHENETTE (13 ROOMS W/O KITCHENETTTES + 84 EXISTING ROOMS = 97 SPACES); + 0.75 SPACES / EACH EMPLOYEE ON MAX. SHIFT (8 EMPLOYEES * 0.75 SPACES = 6 SPACES); + (2 SPACES FOR SINGLE FAMILY RESIDENCE (1830 CHOCOLATE AVE)) = 105 TOTAL SPACES	104 TOTAL PARKING SPACES	103 TOTAL PARKING SPACES (1 SPACE TO BE REMOVED)	2	2
10	MINIMUM BICYCLE PARKING RATIOS	§225-402.7.A.	2 BIKE SPACES / 50 AUTOMOBILE SPACES (104 AUTOMOBILE SPACES / 2 BIKE SPACES = 5 TOTAL BIKE SPACES	5 TOTAL BIKE SPACES	6 TOTAL BIKE SPACES	NA	NA

* FRONT YARD SETBACK IS BASED ON ZONING §225-206.G. YARD AREA EXCEPTION.
** THE EXPANSION OF THE EXISTING NONCONFORMING BUILDING IS PERMITTED PER ZONING §225-602.A.
*** EXISTING NON-CONFORMING SETBACKS

GENERAL NOTES

1. ALL CONSTRUCTION SHALL COMPLY WITH DERRY TOWNSHIP STANDARDS AND SPECIFICATIONS, DAUPHIN COUNTY STANDARDS AND SPECIFICATIONS, PENNSYLVANIA DEPARTMENT OF TRANSPORTATION STANDARDS AND SPECIFICATIONS, 2010 ADA STANDARDS, AND STATE BUILDING CODE IN THE ABOVE REFERENCED INCREASING HIERARCHY. IF SPECIFICATIONS ARE IN CONFLICT, THE MORE STRINGENT SPECIFICATION SHALL APPLY. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE OSHA, FEDERAL, STATE AND LOCAL REGULATIONS.
2. THE CONTRACTOR SHALL VERIFY ALL SITE AND BUILDING CONDITIONS IN THE FIELD AND CONTACT THE CIVIL ENGINEER AND ARCHITECT IF THERE ARE ANY QUESTIONS OR CONFLICTS REGARDING THE CONSTRUCTION DOCUMENTS AND/OR FIELD CONDITIONS, SO THAT APPROPRIATE REVISIONS CAN BE MADE PRIOR TO BIDDING. ANY CONFLICT BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE CONFIRMED WITH THE OWNER'S CONSTRUCTION MANAGER PRIOR TO BIDDING.
3. DO NOT INTERRUPT EXISTING UTILITIES SERVICING FACILITIES OCCUPIED AND USED BY THE OWNER OR OTHERS DURING OCCUPIED HOURS EXCEPT WHEN SUCH INTERRUPTIONS HAVE BEEN AUTHORIZED IN WRITING BY THE OWNER AND THE LOCAL MUNICIPALITIES. INTERRUPTIONS SHALL ONLY OCCUR AFTER ACCEPTABLE TEMPORARY SERVICE HAS BEEN PROVIDED.
4. THE CONTRACTOR SHALL PROVIDE AS-BUILT RECORD DRAWINGS OF ALL CONSTRUCTION (INCLUDING UNDERGROUND UTILITIES AND STORMWATER SYSTEM) TO THE OWNER AT THE END OF CONSTRUCTION.
5. THE ENGINEER IS NOT RESPONSIBLE FOR SITE SAFETY MEASURES TO BE EMPLOYED DURING CONSTRUCTION. THE CONTRACTOR SHALL COMPLY WITH CFR 29 PART 1926 FOR EXCAVATION, TRENCHING, AND TRENCH PROTECTION REQUIREMENTS.
6. INFORMATION ON EXISTING UTILITIES AND STORM DRAINAGE SYSTEMS HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL OR COUNTY OR STATE RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES AND STORM DRAINAGE SYSTEMS ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UNDERGROUND AND OVERHEAD UTILITIES AND STORM DRAINAGE SYSTEMS INCLUDING SERVICES. PRIOR TO DEMOLITION OR CONSTRUCTION, THE CONTRACTOR SHALL CONTACT PA PENNSYLVANIA811 72 HOURS BEFORE COMMENCEMENT OF WORK AT PA (800) 242-1776 OR AT 811 AND VERIFY ALL UTILITY AND STORM DRAINAGE SYSTEM LOCATIONS. THE CONTRACTOR SHALL EMPLOY THE USE OF A UTILITY LOCATING COMPANY TO PROVIDE SUBSURFACE UTILITY ENGINEERING CONSISTING OF DESIGNATING UTILITIES AND STORM PIPING ON PRIVATE PROPERTY WITHIN THE CONTRACT LIMIT AND CONSISTING OF DESIGNATING AND LOCATING WHERE PROPOSED UTILITIES AND STORM PIPING CROSS EXISTING UTILITIES AND STORM PIPING WITHIN THE CONTRACT LIMITS. SHOULD ANY UNCHARTED OR INCORRECTLY CHARTED, EXISTING PIPING OR OTHER UTILITY BE UNCOVERED DURING EXCAVATION, CONSULT THE CIVIL ENGINEER IMMEDIATELY FOR DIRECTIONS BEFORE PROCEEDING FURTHER WITH WORK IN THIS AREA.
7. IF PLANS AND OR SPECIFICATIONS ARE IN CONFLICT, THE MOST STRINGENT SHALL APPLY.
8. ALL NOTES AND DIMENSIONS DESIGNATED "TYPICAL" APPLY TO ALL LIKE OR SIMILAR CONDITIONS THROUGHOUT THE PROJECT.
9. CONTRACTOR(S) TO TAKE AND VERIFY ALL DIMENSIONS AND CONDITIONS OF THE WORK AND BE RESPONSIBLE FOR COORDINATION OF SAME. FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO START OF WORK.
10. NO CONSTRUCTION OR DEMOLITION SHALL BEGIN UNTIL APPROVAL OF THE FINAL PLANS IS GRANTED BY ALL GOVERNING AND REGULATORY AGENCIES.
11. THE OWNER IS RESPONSIBLE FOR OBTAINING ALL NECESSARY ZONING PERMITS REQUIRED BY GOVERNMENT AGENCIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT AND OBTAIN FROM DAUPHIN COUNTY AND DERRY TOWNSHIP ALL CONSTRUCTION PERMITS, INCLUDING ANY PENNDOT PERMITS, SEWER AND WATER CONNECTION PERMITS, AND ROADWAY CONSTRUCTION PERMITS. THE CONTRACTOR SHALL POST ALL BONDS, PAY ALL FEES, PROVIDE PROOF OF INSURANCE AND PROVIDE TRAFFIC CONTROL NECESSARY FOR THIS WORK.
12. THE CONTRACTOR SHALL RESTORE ANY UTILITY STRUCTURE, DRAINAGE STRUCTURE, PIPE, UTILITY, PAVEMENT, CURBS, SIDEWALKS, LANDSCAPED AREAS, SWALE, PAVEMENT MARKINGS, OR SIGNAGE DISTURBED DURING DEMOLITION AND/OR CONSTRUCTION TO THEIR ORIGINAL CONDITION OR BETTER, AS APPROVED BY THE CIVIL ENGINEER, AND TO THE SATISFACTION OF THE OWNER AND DERRY TOWNSHIP.
13. THE SITE IS CURRENTLY SERVICED BY PUBLIC WATER AND PUBLIC SEWER.
14. NO PART OF THE PROJECT PARCEL IS LOCATED WITHIN ANY FEMA DESIGNATED FLOOD HAZARD AREAS.
15. THERE ARE NO WETLANDS LOCATED ON THE SITE.
16. ALL CONSTRUCTION WITHIN A PENNDOT RIGHT OF WAY SHALL COMPLY WITH ALL DEPARTMENT OF TRANSPORTATION STANDARDS AND SPECIFICATIONS.
17. A HIGHWAY OCCUPANCY PERMIT IS REQUIRED PURSUANT TO §420 OF THE ACT OF JUNE 1, 1945 (P.L. 1242, NO. 428), AS AMENDED, BEFORE ANY IMPROVEMENTS ARE INITIATED WITHIN A STATE HIGHWAY, OR STREET, ACCESS DRIVE, OR DRIVEWAY INTERSECTION TO A STATE HIGHWAY IS PERMITTED.
18. THE DEVELOPER/CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE A MINIMUM OF 24-HOURS NOTICE AND TO COORDINATE WITH THE TOWNSHIP/TOWNSHIP ENGINEER IN REGARDS TO ALL MUNICIPAL INSPECTION WORK REQUIRED ON THE PROJECT SITE.
19. THE EXISTING STORMWATER BMPS ARE DESIGNED TO ALLOW 57,935 SF / 1.33 AC. OF IMPERVIOUS AREA ON THE LOT PER RECORDED INSTRUMENT 20180024570. A SEPARATE APPROVAL IS REQUIRED FOR ANY IMPERVIOUS AREA PROPOSED BEYOND THE DESIGN LIMIT OR OTHERWISE NOT IN CONFORMANCE WITH THIS PLAN.
20. TOWNSHIP STAFF IS GRANTED PERMISSION TO ACCESS THE DRAINAGE EASEMENT FROM THE NEAREST RIGHT-OF-WAY.
21. ALL CONSTRUCTION SHALL CONFORM TO PENNDOT PUBLICATIONS 408 AND 72 STANDARDS AND ALL APPLICABLE DERRY TOWNSHIP ORDINANCES

REFERENCED PLANS

PRELIMINARY/FINAL SUBDIVISION AND LAND DEVELOPMENT PLAN FOR 1806 E. CHOCOLATE AVENUE RED ROOF INN SITE (INST. 20180024570 RECORDED 09/28/2018)
BEST WESTERN PLUS PARKING ADDITION PLAN (LAST REVISED 06/01/2022).

AS-BUILT PLAN FOR 1806 CHOCOLATE AVENUE RED ROOF INN SITE AS PREPARED BY DAWOOD ENGINEERING DATED JUNE 2022

SHEET INDEX

#	SHEET TITLE
01	COVER SHEET
02	EXISTING CONDITIONS PLAN
03	DEMOLITION PLAN
04	SUBDIVISION PLAN
05	PROPOSED CONDITIONS PLAN
06	EASEMENT PLAN
07	DETAILS
08	E&S CONTROL PLAN
09	DETAILS
10	DETAILS

SUPPLEMENTAL PLANS:
- LIGHTING PLAN

TOWNSHIP OF DERRY

PLAT NO.
SUBMISSION DATE:
AUGUST 04 2026
MONTH DAY YEAR
REVISION DATE:
MONTH DAY YEAR
MONTH DAY YEAR
MONTH DAY YEAR
MONTH DAY YEAR
MONTH DAY YEAR
MONTH DAY YEAR
MONTH DAY YEAR

SIG. DIRECTOR OF COMMUNITY DEVELOPMENT

I, ZANE GIEST, P.E., HEREBY CERTIFY THAT THE SWM SITE PLAN MEETS ALL DESIGN STANDARDS AND CRITERIA OF THE TOWNSHIP OF DERRY SWM ORDINANCE, CH. 174.

ENGINEER: _____
DATE: _____

I, _____, ACKNOWLEDGE THAT THE STORMWATER BMPS ARE FIXTURES THAT CANNOT BE ALTERED OR REMOVED WITHOUT PRIOR APPROVAL BY THE TOWNSHIP.

LANDOWNER: _____
DATE: _____

STATE OF _____
COUNTY OF _____

ON THIS_____DAY OF _____, BEFORE ME, THE UNDERSIGNED PERSONALLY APPEARED _____,

WHO BEING DULY SWORN ACCORDING TO LAW DEPOSES AND SAYS THAT THEY ARE OWNER OF THE PROPERTY SHOWN ON THIS PLAT AND THAT THEY ACKNOWLEDGE THE SAME TO BE THEIR ACT AND PLAN AND DESIRE THE SAME TO BE RECORDED AS SUCH ACCORDING TO LAW.

_____
WITNESS MY HAND AND SEAL THE DAY AND DATE WRITTEN
MY COMMISSION EXPIRES: _____ **NOTARY PUBLIC**

STATE OF _____
COUNTY OF _____

ON THIS_____DAY OF _____, BEFORE ME, THE UNDERSIGNED PERSONALLY APPEARED _____,

WHO BEING DULY SWORN ACCORDING TO LAW DEPOSES AND SAYS THAT THEY ARE OWNER OF THE PROPERTY SHOWN ON THIS PLAT AND THAT THEY ACKNOWLEDGE THE SAME TO BE THEIR ACT AND PLAN AND DESIRE THE SAME TO BE RECORDED AS SUCH ACCORDING TO LAW.

_____
WITNESS MY HAND AND SEAL THE DAY AND DATE WRITTEN
MY COMMISSION EXPIRES: _____ **NOTARY PUBLIC**

THIS PLAN REVIEWED BY DAUPHIN COUNTY PLANNING COMMISSION THIS _____ DAY OF _____, 20__.

CHAIRMAN: _____
SECRETARY: _____

THIS PLAN RECOMMENDED FOR APPROVAL BY THE DERRY TOWNSHIP PLANNING COMMISSION THIS _____ DAY OF _____, 2024.

CHAIRMAN: _____
SECRETARY: _____

THIS PLAN APPROVED BY THE DERRY TOWNSHIP SUPERVISORS THIS _____ DAY OF _____, 2024.

CHAIRMAN: _____
SECRETARY: _____

SURVEYOR
I HEREBY CERTIFY THAT THIS PLAN TO BE CORRECT AS SHOWN.

ENGINEER
I HEREBY CERTIFY THAT THIS PLAN TO BE CORRECT AS SHOWN.

WETLAND
I, ZANE E. GEIST, P.E., HEREBY CERTIFY THAT THERE ARE NO WETLANDS ON THE SUBJECT PROPERTY, THE PROPOSED PROJECT WILL NOT IMPACT OFF-SITE WETLANDS, AND WETLAND PERMITS ARE NOT REQUIRED FROM THE STATE OR FEDERAL GOVERNMENT.

ENGINEER: _____
DATE: _____

PRELIMINARY/FINAL SUBDIVISION AND LAND DEVELOPMENT PLAN OF


PROPOSED BUILDING ADDITION AT BEST WESTERN PLUS

SITUATED IN DERRY TOWNSHIP, DAUPHIN COUNTY

OWNER:

SWEET HOTELS, LLC

DATE: 08/04/2026 **DWN BY: MLS** **DWG NO.: 25-0531** **SHEET 01 OF 10**



LEGEND

- EXISTING PROPERTY LINE
- EXISTING RIGHT-OF-WAY LINE
- EXISTING SETBACK
- EXISTING PROPERTY CORNER
- 350 EXISTING MAJOR CONTOUR
- 349 EXISTING MINOR CONTOUR
- EXISTING LIDAR CONTOUR
- OE EXISTING OVERHEAD ELECTRIC
- UE EXISTING UNDERGROUND ELECTRIC
- EXISTING UTILITY POLE
- EXISTING GUY WIRE
- Lt EXISTING LIGHT STANDARD
- Ep EXISTING ELECTRIC BOX
- G EXISTING GAS LINE
- Gv EXISTING GAS VALVE
- Gm EXISTING GAS METER
- Fh EXISTING WATER HYDRANT
- Wv EXISTING WATERVALVE
- S EXISTING SANITARY SEWER LINE
- EXISTING SANITARY MANHOLE
- EXISTING STORM MANHOLE
- Co EXISTING SANITARY CLEANOUT
- EXISTING INLET STRUCTURE
- EXISTING STORM PIPE
- EXISTING SUBSURFACE SWM FACILITY
- EXISTING SIGN
- Co EXISTING ROOF DRAIN
- RD EXISTING ROOF DRAIN
- EXISTING EDGE OF MACADAM
- EXISTING STRIPING
- EXISTING EDGE OF CONCRETE
- EXISTING CURB
- x EXISTING FENCE
- EXISTING TREE OR SHRUB
- ZONING/MUNICIPAL/COUNTY BOUNDARY
- EXISTING EASEMENT
- EXISTING MUNICIPAL MONUMENT OR BENCHMARK

SURVEY NOTES

1. TOPOGRAPHIC & BOUNDARY INFORMATION IS BASED ON A FIELD SURVEY DAWOOD ENGINEERING, INC. IN JUNE 2022. AS CONSTRUCTED SURVEY UPDATED BY DAWOOD IN JUNE 2024 AND UPDATED BY INTEGRATED CONSULTING IN JULY 2026.
2. SUBSURFACE UTILITIES ARE SHOWN RELATIVE TO THE LOCATION OF THEIR SURFACE FEATURE LOCATIONS. THE SURVEYOR DOES NOT WARRANT THAT THEIR UNDERGROUND LOCATIONS ARE COMPLETE OR EXACT. THE SURVEYOR HAS NOT LOCATED THE SUBSURFACE UTILITIES.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT.
4. PLAN BEARING BASE IS REFERENCED TO PENNSYLVANIA STATE PLANE – SOUTH ZONE NAD 83 (CORS 96).
5. APPROXIMATE ADJACENT PROPERTY BOUNDARIES AND ADJACENT PROPERTY OWNER INFORMATION ARE SHOWN PER RECORDED INSTRUMENT NO. 20180024570.
6. THERE ARE NO KNOWN KARST FEATURES OR SINKHOLES ON OR NEAR THE PROPERTY.

SOILS INFORMATION

DuB2 DUFFIELD SILT LOAM, 3-8% SLOPES, MODERATELY ERODED, HSG-B, HYDRIC

GEOLOGY INFORMATION

Oe EPLER FORMATION

PROPERTY MARKER TABLE

MARKER #	NORTHING	EASTING
M1	354302.244	2286045.055
M2	354405.842	2286249.507
M3	354260.105	2286308.969
M4	354290.903	2286392.718
M5	354286.369	2286394.867
M6	354311.595	2286438.266
M7	354197.735	2286531.386
M8	354160.833	2286444.820
M9	354130.243	2286362.151
M10	354050.476	2286146.572
M11	354446.107	2286328.970
M12	354454.754	2286346.036
M13	354456.534	2286345.122
M14	354458.371	2286348.694
M15	354456.591	2286349.609
M16	354463.119	2286362.104
M17	354331.356	2286430.475
M18	354305.412	2286385.840

INTEGRATED CONSULTING
4 KACEY COURT
MECHANICSBURG | PA | 17055
717.386.1362
www.IntegratedConsultingLLC.com

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

PROPOSED BUILDING ADDITION

AT

BEST WESTERN PLUS

DAUPHIN COUNTY

DERRY TOWNSHIP

PROFESSIONAL SEAL

DRAWN	NJL
REVIEWED	ZEG / JLK
SCALE	AS NOTED
DATE	08/04/2026
PROJECT NO.	25-0531
CAD FILE:	02 - EXISTING CONDITIONS

REVISIONS		
NO.	DATE	DESCRIPTION

TITLE

EXISTING CONDITIONS PLAN

SHEET NO.


02 of 10

SCALE: 1"= 20'

B:\2026_DEFAULT_CUSES\DEFAULT DESKTOP\MERSHUM\INTEGRATED DEVELOPMENT PARTNERS, LLC\DP - 25-0531\PROJECTS\2025\25-0531 1898 CHOCOLATE AVE ADDITION\DWG\02 - EXISTING CONDITIONS PLAN.

© 2026 INTEGRATED CONSULTING (IC). THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF IC.

FOR PERMITTING PURPOSES ONLY. NOT FOR CONSTRUCTION.



LEGEND

- DEMOLISH CONCRETE
- PROPOSED SAW CUT LINE
- TBD — DENOTES A FEATURE TO BE DEMOLISHED
- DEMOLISH BUILDING
- DEMOLISH MACADAM

DEMOLITION PLAN NOTES

1. ALL BUILDINGS, INCLUDING FOUNDATION WALLS AND FOOTINGS AND BASEMENT SLABS INDICATED ON THE DEMOLITION PLAN ARE TO BE REMOVED FROM THE SITE. CONTRACTOR SHALL SECURE ANY PERMITS, PAY ALL FEES AND PERFORM CLEARING AND GRUBBING AND DEBRIS REMOVAL PRIOR TO COMMENCEMENT OF GRADING OPERATIONS.
2. SEDIMENT AND EROSION CONTROLS AS SHOWN ON THE SEDIMENT AND EROSION CONTROL PLAN AND/OR DEMOLITION PLAN SHALL BE INSTALLED BY THE DEMOLITION CONTRACTOR PRIOR TO START OF DEMOLITION AND CLEARING AND GRUBBING OPERATIONS.
3. REMOVE AND DISPOSE OF ANY SIDEWALKS, FENCES, STAIRS, WALLS, DEBRIS AND RUBBISH REQUIRING REMOVAL FROM THE WORK AREA IN AN APPROVED OFF SITE LANDFILL, BY AN APPROVED HAULER. HAULER SHALL COMPLY WITH ALL REGULATORY REQUIREMENTS.
4. THE CONTRACTOR SHALL SECURE ALL PERMITS FOR HIS DEMOLITION AND DISPOSAL OF HIS DEMOLITION MATERIAL TO BE REMOVED FROM THE SITE. THE CONTRACTOR SHALL POST BONDS AND PAY PERMIT FEES AS REQUIRED. BUILDING DEMOLITION CONTRACTOR SHALL BE RESPONSIBLE FOR PERMITS AND DISPOSAL OF ALL BUILDING DEMOLITION DEBRIS IN AN APPROVED OFF-SITE LANDFILL.
5. THE CONTRACTOR SHALL CUT AND PLUG, OR ARRANGE FOR THE APPROPRIATE UTILITY PROVIDER TO CUT AND PLUG ALL SERVICE PIPING AT THE STREET LINE OR AT THE MAIN, AS REQUIRED BY THE UTILITY PROVIDER, OR AS OTHERWISE NOTED OR SHOWN ON THE CONTRACT DRAWINGS. ALL SERVICES MAY NOT BE SHOWN ON THIS PLAN. THE CONTRACTOR SHALL INVESTIGATE THE SITE PRIOR TO BIDDING TO DETERMINE THE EXTENT OF SERVICE PIPING TO BE REMOVED, CUT OR PLUGGED. THE CONTRACTOR SHALL PAY ALL UTILITY PROVIDER FEES FOR ABANDONMENTS AND REMOVALS.
6. THE CONTRACTOR SHALL PROTECT ALL IRON PINS, MONUMENTS AND PROPERTY CORNERS DURING DEMOLITION AND CONSTRUCTION ACTIVITIES. ANY CONTRACTOR DISTURBED PINS, MONUMENTS, AND OR PROPERTY CORNERS, ETC. SHALL BE RESET BY A LICENSED LAND SURVEYOR AT THE EXPENSE OF THE CONTRACTOR.
7. THE DEMOLITION CONTRACTOR SHALL STABILIZE THE SITE AND KEEP EROSION CONTROL MEASURES IN PLACE UNTIL THE COMPLETION OF HIS WORK OR UNTIL THE COMMENCEMENT OF WORK BY THE SITE CONTRACTOR, WHICHEVER OCCURS FIRST, AS REQUIRED OR DEEMED NECESSARY BY THE ENGINEER OR OWNER'S REPRESENTATIVE. THE SITE CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR THE MAINTENANCE OF EXISTING EROSION AND SEDIMENTATION CONTROLS AND FOR INSTALLATION OF ANY NEW SEDIMENT AND EROSION CONTROLS AS PER THE SEDIMENT AND EROSION CONTROL PLAN, AT THAT TIME..
8. BACK FILL DEPRESSIONS, FOUNDATION HOLES AND REMOVED DRIVEWAY AREAS IN LOCATIONS NOT SUBJECT TO FURTHER EXCAVATION WITH SOIL MATERIAL APPROVED BY THE OWNER'S GEOTECHNICAL ENGINEER AND COMPACT, FERTILIZE, SEED AND MULCH DISTURBED AREAS NOT SUBJECT TO FURTHER SITE CONSTRUCTION. DEMOLISHED BUILDING FOUNDATION AREA AND BASEMENT IF PRESENT TO BE BACKFILLED WITH GRAVEL FILL OR MATERIAL SPECIFIED IN THE PROJECT GEOTECHNICAL REPORT IN LIFT THICKNESS SPECIFIED IN THE GEOTECHNICAL REPORT. COMPACT TO 95% MAX. DRY DENSITY PER ASTM D1557 AT MOISTURE CONTENT SPECIFIED IN GEOTECHNICAL REPORT AND EARTHWORK SPECIFICATION. EMPLOY WATERING EQUIPMENT FOR DUST CONTROL.
9. THE CONTRACTOR SHALL CUT AND REMOVE AT LUMINAIRE AND SIGN LOCATIONS ANY PROTRUDING CONDUITS TO 24" BELOW GRADE. THE CONTRACTOR SHALL REMOVE ALL CABLE AND CONDUCTORS FROM REMAINING LIGHTING AND SIGNING CONDUITS TO BE ABANDONED. ANY REMAINING LIGHTING TO REMAIN IN PLACE SHALL BE RECIRCUITED OR REWIRED AS NECESSARY TO REMAIN IN OPERATION.
10. THE CONTRACTOR SHALL ARRANGE FOR AND INSTALL TEMPORARY OR PERMANENT UTILITY CONNECTIONS WHERE INDICATED ON PLAN OR AS REQUIRED. MAINTAIN UTILITY SERVICES TO BUILDINGS OR TO SERVICES TO REMAIN. CONTRACTOR TO COORDINATE WITH UTILITY PROVIDERS FOR INSTALLATION AND PAY UTILITY PROVIDER FEES.

INTEGRATED CONSULTING
4 KACEY COURT
MECHANICSBURG | PA | 17055
717.386.1362
www.IntegratedConsultingLLC.com

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

PROPOSED BUILDING ADDITION
AT
BEST WESTERN PLUS

DERRY TOWNSHIP DAUPHIN COUNTY

PROFESSIONAL SEAL

DRAWN	NJL
REVIEWED	ZEG / JLK
SCALE	AS NOTED
DATE	08/04/2026
PROJECT NO.	25-0531
CAD FILE:	02.5 - DEMOLITION PLAN

REVISIONS NO.	DATE	DESCRIPTION

TITLE
DEMOLITION PLAN

SHEET NO.
03 of 10

©2026 INTEGRATED CONSULTING (IC). THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF IC.

FOR PERMITTING PURPOSES ONLY. NOT FOR CONSTRUCTION.

8/2026, DEFAULT, C:\USERS\DEFAULT.DESKTOP-M3BSHHM\DROPBOX\INTEGRATED DEVELOPMENT PARTNERS, LLC\DP - DATA\PROJECTS\2025\25-0531 1098 CHOCOLATE AVE ADDITION\DWG\02.5 - DEMOLITION PLAN.DWG 04 DEMOLITION PLAN

LEGEND

PROPOSED PROPERTY LINE
PROPOSED YARD SETBACK LINE
PROPOSED IRON PIN
PROPERTY CORNER MARKER

East Chocolate Avenue
(U.S. 0422 - S.R. 0422)
R/W Width Varies

228.76
S63° 07' 42"W

271.52
S21° 57' 10"E

N22° 02' 41"W
157.37

1800 CHOCLATE AVE
89,006 SF
2.04 ACRES

N/F Tai Kim Nguyen
Tax Parcel No. 24-007-126

N/F William E. Hoffer & Deborah L. Hoffer
PIN: 24-007-129-000-0000
Deed Book 2190, Page 17
Tract No. 1
Being 1820 and 1822 East Chocolate Ave

N/F Damon S. Collins et ux
PIN: 24-007-131-000-0000
Inst. No.: 20170027057

N/F Kenneth F. Bishop, Jr. & Kristi N. Bishop
PIN: 24-007-132-000-0000
Deed Book 4101, Page 147

S62° 47' 49"W
4.02
S27° 11' 25"E
2.00
N27° 13' 08"W
2.00
19.13
S63° 07' 41"W
14.10
S62° 24' 58"W

1830 CHOCLATE AVE
5,766 SF
0.13 ACRES

18.69
S22° 05' 34"E
N27° 22' 29"W
148.45

N65° 41' 30"E
20.14

41.79
S22° 00' 33"E
39.36
S26° 36' 04"E

N59° 49' 57"E
28.11

S25° 21' 40"E
16.06

21' Wide Unnamed Alley

N31° 42' 30"W
21.01

89.23
S69° 48' 36"W

6' PVC / Vinyl Fence

24.33
S89° 49' 57"W

16' Wide Unnamed Alley

21' Wide Unnamed Alley

N07° 16' 38"W
141.69

N89° 41' 05"E
318.01

N66° 54' 44"E
94.10

N/F NGUYEN, TAI KIM
TAX PARCEL NO. 24-007-222

N/F Margaret L. Dunn
Tax Parcel No. 24-007-155

N/F Colleen M. Raber
Tax Parcel No. 24-007-158

N/F Scott H. Smith
Tax Parcel No. 24-007-166

17

20' 10' 0' 20'
SCALE: 1"= 20'

INTEGRATED CONSULTING
4 KACEY COURT
MECHANICSBURG | PA | 17055
717.386.1362
www.IntegratedConsultingLLC.com

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

PROPOSED BUILDING ADDITION

AT

BEST WESTERN PLUS

DERRY TOWNSHIP DAUPHIN COUNTY

PROFESSIONAL SEAL

DRAWN	NJL
REVIEWED	ZEG / JLK
SCALE	AS NOTED
DATE	08/04/2026
PROJECT NO.	25-0531
CAD FILE: 05 - SUBD PLAN	

REVISIONS NO.	DATE	DESCRIPTION

TITLE

SUBDIVISION PLAN


SHEET NO.

04 of 10

© 2026 INTEGRATED CONSULTING (IC). THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF IC.

FOR PERMITTING PURPOSES ONLY. NOT FOR CONSTRUCTION.

S:\2026_DEFAULT_C:\USERS\EDEFAULT.DESKTOP-A2E5SNH\APPDATA\ROAMING\DROPBOX\INTEGRATED DEVELOPMENT PARTNERS, LLC\DP - SHARED\PROJECTS\2025\25-0531 1800 CHOCOLATE AVE ADDITION\DWG\LDDS - SUBD PLAN.DWG\LDDS SUBDIVISION PLAN



LEGEND

- EXISTING PROPERTY LINE
- EXISTING RIGHT-OF-WAY LINE
- PROPOSED YARD SETBACK LINE
- PROPOSED BUILDING
- PROPOSED CONCRETE
- PROPOSED STANDARD DUTY PAVEMENT
- PROPOSED PERVIOUS PAVEMENT
- 310 — PROPOSED MAJOR CONTOUR
- 309 — PROPOSED MINOR CONTOUR
- 307.66 — PROPOSED SPOT ELEVATION
- 1.0% 3:1 — PROPOSED SLOPE ARROWS
- RD RD — PROPOSED ROOF DRAIN
- CO — PROPOSED CLEANOUT
- DS — PROPOSED DOWNSPOUT
- PROPOSED STRIPING
- PROPOSED IRON PIN
- PROPERTY CORNER MARKER
- (2) — PROPOSED PARKING TOTAL

PROPOSED CONDITIONS NOTES

1. THE CONTRACTOR SHALL FOLLOW THE SEQUENCE OF CONSTRUCTION NOTES PROVIDED ON THE SEDIMENT AND EROSION CONTROL PLAN.
2. THE CONTRACTOR SHALL REFERENCE ARCHITECTURAL PLANS FOR EXACT DIMENSIONS AND CONSTRUCTION DETAILS OF BUILDING, ANY RAISED CONCRETE SIDEWALKS, LANDINGS, RAMPS, AND STAIRS.
3. ALL SITE DIMENSIONS ARE REFERENCED TO THE FACE OF CURBS OR EDGE OF PAVING AS APPLICABLE UNLESS OTHERWISE NOTED. ALL BUILDING DIMENSIONS ARE REFERENCED TO THE OUTSIDE FACE OF THE STRUCTURE.
4. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TRAFFIC DEVICES FOR PROTECTION OF VEHICLES AND PEDESTRIANS AS REQUIRED BY THE OWNER, ENGINEER OR LOCAL GOVERNING AUTHORITIES.
5. THE CONTRACT LIMIT IS THE PROPERTY LINE UNLESS OTHERWISE SPECIFIED OR SHOWN ON THE CONTRACT DRAWINGS.
6. ALL ADA DESIGNATED PARKING STALLS, ACCESS AISLES AND PEDESTRIAN WALKWAYS SHALL CONFORM TO THE CURRENT VERSION OF THE AMERICANS WITH DISABILITIES ACT STANDARDS FOR ACCESSIBLE DESIGN AND ANSI STANDARDS AND MAY BE SUPERCEDED BY THE STATE BUILDING CODE.
7. CONSTRUCTION OCCURRING ON THIS SITE SHALL COMPLY WITH NFPA 241 STANDARD FOR SAFEGUARDING CONSTRUCTION, ALTERATION AND DEMOLITION OPERATIONS, AND CHAPTER 16 OF NFPA 1 UNIFORM FIRE CODE.
8. THE CONTRACTOR SHALL PRESERVE EXISTING VEGETATION WHERE POSSIBLE AND/OR AS NOTED ON DRAWINGS. REFER TO SEDIMENT AND EROSION CONTROL PLAN FOR LIMIT OF DISTURBANCE AND EROSION CONTROL NOTES.
9. TOPSOIL SHALL BE STRIPPED AND STOCKPILED ON SITE FOR USE IN FINAL LANDSCAPING.
10. BUILDING UTILITY PENETRATIONS AND LOCATIONS ARE SHOWN FOR THE CONTRACTOR'S INFORMATION AND SHALL BE VERIFIED WITH THE BUILDING MEP, STRUCTURAL, AND ARCHITECTURAL DRAWINGS AND WITH THE OWNER'S CONSTRUCTION MANAGER.
11. SITE CONTRACTOR SHALL PROVIDE ALL BENDS, FITTINGS, ADAPTERS, ETC., AS REQUIRED FOR PIPE CONNECTIONS TO BUILDING STUB OUTS, INCLUDING ROOF/FOOTING DRAIN CONNECTIONS TO ROOF LEADERS AND TO STORM DRAINAGE SYSTEM OR AS SHOWN ON PLAN.
12. THE CONTRACTOR SHALL BE RESPONSIBLE TO REMOVE ANY DEBRIS AND FLUSH OUT ALL EXISTING AND PROPOSED STORM DRAINAGE FACILITIES WITHIN THE PROJECT LIMITS AT THE COMPLETION OF CONSTRUCTION.

INTEGRATED CONSULTING
4 KACEY COURT
MECHANICSBURG | PA | 17055
717.386.1362
www.IntegratedConsultingLLC.com

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

PROPOSED BUILDING ADDITION

AT

BEST WESTERN PLUS

DERRY TOWNSHIP — DAUPHIN COUNTY

PROFESSIONAL SEAL

DRAWN	NJL
REVIEWED	ZEG / JLK
SCALE	AS NOTED
DATE	08/04/2026
PROJECT NO.	25-0531
CAD FILE:	03 - PROPOSED CONDITIONS

REVISIONS NO.	DATE	DESCRIPTION

TITLE

PROPOSED CONDITIONS PLAN

SHEET NO.

05 of 10

©2026 INTEGRATED CONSULTING (IC). THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF IC.

FOR PERMITTING PURPOSES ONLY. NOT FOR CONSTRUCTION.

9/2026, DEFAULT, C:\USERS\DEFAULT.DESKTOP-BSSSBNM\TGRATED DEVELOPMENT PARTNERS, LLC\DP - I\N\PROJECTS\2025\25-0531 1804 CHOCOLATE AVE ADDITION\WORKFILES\03 - PROPOSED CONDITIONS\DWG\05 PROPOSED CONDITIONS PLAN